

Red line · 160 KIAS

V_{NE} — never exceed

Yellow arc · 128–160 KIAS

Caution range
Smooth air only

White arc · 41–85 KIAS

Full-flap operating range
From V_{S0} (stall, landing configuration) up to V_{FE} (flaps-extended limit)

Green arc · 47–128 KIAS

Normal operating range
From V_{S1} (stall, flaps up) up to V_{NO} (maximum structural cruising speed)

Not marked on the dial: V_A (manoeuvring speed) — 97 KIAS at 2300 lb